

**NEW CONSTRUCTION AND
LAND DISTURBANCE**

GOAL:

Comply with the village's
construction and post-construction
minimum control measures

PRECAUTIONARY STEPS

- **Plan the construction and/or land clearing activities so that the soil is not exposed for long periods of time**
- Minimize compaction of soils
- Minimize impervious cover
- Maximize opportunities



- **Install sediment control devices before disturbing soil**
- **Limit grading to small areas**
- **Stabilize site to protect against sediment runoff**
- **Protect against sediment flowing into storm drains**



- **Maintain native vegetation (especially near waterways)**
- **Install sediment barriers on slopes or divert stormwater**
- **Inspect erosion and sediment controls (ES&C) devices**
- **Inspect ES&C devices during storm or snow melt events**

